



AZOOM United Co.

العرض المالي

FINANCIAL OFFER

مقدم من

شركة عزوم المتحدة للمقاولات

لصالح



مشاريع ضمان

DAMAN PROJECTS

لمنافسة

تنفيذ اعمال التشغيليات الداخلية والخارجية لمشروع قلب نجد بالرياض

التاريخ: 2026/07/16

الرقم: (110357)



ضمان السرية وحقوق الطبع والنشر والنسخ

CONFIDENTIALITY & COPYRIGHT

لا يجوز إفشاء هذا العرض وجميع المستندات المقدمة — سواء كانت إلكترونية أو ورقية — وهي مخصصة للتقييم الداخلي والنظر والدراسة فقط. ليس هناك جزء من هذه الوثيقة قد نُسخ أو نُقل بأي وسيلة (إلكترونية أو ورقية أو تسجيل أو أي وسيلة كانت) من غير إذن خطي مسبق من قبل شركة عزوم المتحدة للمقاولات.

ويحتوي هذا العرض وأي مستندات داعمة على معلومات سرية بالنسبة لشركة عزوم المتحدة للمقاولات، وتم تقديمها على أساس أنها يجب ألا تُستخدم بأي شكل أو تُفشى إلى أي طرف ثالث بشكل كلي أو جزئي — باستثناء موظفي أو مستشاري العميل لأجل اعتبار هذا العرض — أو خلاف ذلك بموافقة خطية مسبقة من عزوم المتحدة للمقاولات.

كافة المعلومات والعروض والبيانات والآراء والمقترحات بهذا العرض وأي مستندات داعمة هي — حسب علمنا — صحيحة ودقيقة، لكنها لا يُقصد بها (ولا يجب أن تؤخذ) تشكيل عرض قابل للقبول أو مُلزم على نحو دائم، ما لم تصبح موضوعاً لاتفاق منفصل ومحدد بين الطرفين. نتطلع إلى مناقشة أي مواضيع تتعلق بنطاق العمل المقترح من قبلنا أو أي معلومات أخرى تكونون في حاجة لها لدعم احتياجاتكم.



COVER LETTER

خطاب العرض المالي

المحترمين

السادة / شركة ضمان

السلام عليكم ورحمة الله وبركاته،،

تحية طيبة وبعد،،

يسعدنا أن نتقدم لكم بالشكر الجزيل على ثقتكم بشركتنا. ومرفق لكم العرض المالي والفني لتنفيذ أعمال «تنفيذ أعمال التشطيبات الداخلية والخارجية لمشروع قلب نجد بالرياض»، بقيمة (14,871,394.53) ريال سعودي — أربعة عشر مليوناً وثمانمائة وواحد وسبعون ألفاً وثلاثمائة وأربعة وتسعون ريالاً وثلاثة وخمسون هلاله لا غير — غير شاملة ضريبة القيمة المضافة، وذلك حسب الكميات ووفق العرض الفني المرفق أدناه.

إجمالي العرض: (14,871,394.53) ريال سعودي

(غير شاملة ضريبة القيمة المضافة)

وتفضلوا بقبول وافر التحية والتقدير،،

الرئيس التنفيذي

م. يحيى آل سلامة





ملخص العرض المالي

FINANCIAL SUMMARY

Amount / القيمة (ريال)	Section / القسم	#
10,393,288.65	Finishes Interior / التشطيبات الداخلية	1
3,819,595.06	Works Landscape / أعمال اللاندسكيب	2
658,510.83	Lighting Works / أعمال الإنارة	3
14,871,394.53	TOTAL (excl. VAT) / الإجمالي قبل الضريبة	
2,230,709.18	VAT 15% / ضريبة القيمة المضافة 15%	
17,102,103.71	TOTAL incl. VAT / الإجمالي شامل الضريبة	

- صلاحية العرض 30 يوم من تاريخ الإصدار.





عزوم المتحدة | قلب نجد — التشطيبات الداخلية

الإجمالي Amount	السعر Rate	الوحدة Unit	الكمية Qty	Description (EN)	البند Code
5.0 — الأعمال المعدنية / القسم 5 - DIVISION 5 - METAL WORKS					
76,260.00	76,260.00	No	1.00	Helical Stair (total length 9.0m, vertical height 3.5m)	5.1.1
27,830.25	27,830.25	Item	1.00	4mm BMT aluminum plate spray lacquered coating; 1500mm high (Balustrade)	5.2.1
16,740.00	16,740.00	Item	1.00	Curved handrail 38mm dia x 1.5mm BMT Brass tube	5.4.1
23,436.00	488.25	m²	48.00	BMT aluminum plate 4mm thick, welded/polished, spray lacquered	5.5.1
3,830.11	531.96	m²	7.20	BMT aluminum wall panel 5mm thick, welded/polished, spray lacquered	5.6.1
61,946.51	599.85	m²	103.27	Screen 6mm thick BMT aluminum sheet spray lacquered (GF lobby S/N, mezz toilet N)	5.7.1
37,238.13	2,511.00	m²	14.83	Metal counter BMT brass plate 2.0mm thick welded/polished (GF lobby)	5.8.1
541,303.71	1,720.50	m²	314.62	Brass sheet screen 6mm thick Brass ornament polished (GF lobby S/N)	5.9.1
8.0 — الأبواب والنوافذ / القسم 8 - DIVISION 8 - DOORS AND WINDOWS					
68,000.00	17,000.00	Item	4.00	KONE automated electronic turnstile w/ access control & fire alarm, polycarbonate leaf (1900x1020mm) DR4	8.1.1
102,765.00	6,045.00	No	17.00	Solid core door 18mm natural stone facing, factory lacquer reverse (5241 4.3)	8.1.2
9,672.00	4,836.00	No	2.00	FRR -/60/60sm steel fire/smokestop door, hold-open, 18mm stone facing (5241 4.1)	8.1.3
85,932.00	3,906.00	No	22.00	FRR -/60/60sm fire/smokestop door, factory lacquer (5241 4.2)	8.1.4
41,600.00	5,200.00	No	8.00	Solid core door 0.5mm BMT brass sheet facing 4/4 sides, brass privacy hardware (5241 4.4)	8.1.5
64,900.00	220.00	No	295.00	Repair shaft door frames in all floors	8.2.1
86,580.00	260.00	No	333.00	Repair and installing door in all floors	8.2.2
2,190.15	730.05	No	3.00	Repair installing civil defense two-paddle door frames	8.2.3
1,171.80	585.90	No	2.00	Repair civil defense door frames	8.2.4
2,245.95	320.85	No	7.00	Repair and installing shaft door frames in all floors	8.2.5
56,680.00	520.00	No	109.00	Repairing civil defense door frames	8.2.6
511,500.00	3,300.00	No	155.00	Civil Defense fire-rated steel door 90 min, double-leaf 1.40m wide, complete	8.3.1
270,000.00	3,600.00	No	75.00	Civil Defense fire-rated steel door 90 min, double-leaf 1.60m wide, complete	8.3.2
633,144.00	2,139.00	No	296.00	Civil Defense fire-rated steel door 90 min, single-leaf 0.90m wide, complete	8.3.3
9.1 — تشطيبات الأرضيات / القسم 9 - DIVISION 9 - FLOOR FINISHES					
1,077,700.40	43.00	m²	25,062.80	MATTE GRAY epoxy coatings incl pathway direction & parking number (all basements & GF)	9.1.1
755,497.00	380.00	m²	1,988.15	30mm natural sandstone tiles with metal inlays, clear sealant (6221 4.4) Stone cladding works shall be carried out in accordance with the approved site samples, using either Travertine stone, White stone, or Khashabi stone, as approved by the Engineer/Consultant.	9.1.2
173,804.63	60.45	m²	2,875.18	Interlock bricks flooring incl reinforcement, control joints, sealant	9.1.3



83,807.88	37.20	Lm	2,252.90	150mm precast concrete curbstone incl 100mm concrete base	9.1.4
10,881.00	60.45	m²	180.00	Wet area waterproofing - Ground to 57th floor (20mm screed + 2 coats rubberized bitumen)	9.1.5.1
17,680.00	52.00	m²	340.00	Wet area waterproofing - Typical floor North tower	9.1.5.2
13,104.00	52.00	m²	252.00	Wet area waterproofing - From 54th to 56th floor	9.1.5.3
101,400.00	52.00	m²	1,950.00	Wet area waterproofing - From 25th to 56th floor	9.1.5.4
152,427.00	102.30	Lm	1,490.00	10mm x 25mm BRASS flooring inserts polished for elevator (4910 4.1)	9.1.6.1
9.2 — تشطيبات الجدران / القسم 9 - WALL FINISHES					
144,558.48	24.00	m²	6,023.27	Repair/supply/apply 20mm wall plaster - INTERNAL	9.2.1
817,091.40	340.00	m²	2,403.21	30mm natural sandstone lining/cladding panel, honed finish (4271 4.1)	9.2.2
31,250.79	1,069.50	m²	29.22	1.5mm BMT brass sheet lift door jamb/head polished - B3 (4940 4.31)	9.2.3.1
50,886.81	1,069.50	m²	47.58	1.5mm BMT brass sheet lift door jamb/head polished - B2	9.2.3.2
46,491.17	1,069.50	m²	43.47	1.5mm BMT brass sheet lift door jamb/head polished - B1	9.2.3.3
46,491.17	1,069.50	m²	43.47	1.5mm BMT brass sheet lift door jamb/head polished - Ground Floor	9.2.3.4
43,068.77	1,069.50	m²	40.27	1.5mm BMT brass sheet lift door jamb/head polished - GF Mezz	9.2.3.5
5,626.50	511.50	m²	11.00	Screen cut from 6mm BMT aluminum spray lacquered - Lift car walls	9.2.4.1
2,966.70	269.70	m²	11.00	Grade A toughened vinyl-backed safety glass mirror - Lift car	9.2.5.1
37,479.00	604.50	m²	62.00	Black stainless steel wall panels hairline finish - Lift car	9.2.6.1
72,000.00	24.00	m²	3,000.00	Repair/supply/apply 20mm wall plaster - EXTERNAL (basements)	9.2.7
307,283.76	24.00	m²	12,803.49	Repair/supply/apply paint & anti-carbonation paint - EXTERNAL (basements)	9.2.8
9.3 — تشطيبات الأسقف / القسم 9 - CEILING FINISHES					
46,409.28	24.00	m²	1,933.72	Cement plaster ceiling (all basements & GF)	9.3.1
106,354.80	223.20	m²	476.50	LUXU PVC stretch ceiling membrane w/ LED lighting & aluminium frame (5331 4.3)	9.3.2
85,962.92	79.05	m²	1,087.45	13mm plasterboard linings - standard system (5113 4.1)	9.3.3
137,617.27	21.39	m²	6,433.72	Repair/supply/apply paint & anti-carbonation paint - Ceiling	9.3.4
8,463.00	604.50	m²	14.00	Black stainless ceiling panels hairline finish - Lift car ceiling	9.3.5
9.4 — الوزرات / القسم 9 - SKIRTING					
158,862.60	167.40	Lm	949.00	Brass skirting formed out of 1.0mm BMT sheet, 18mm plywood backing (4910 4.8)	9.4.1
118,007.59	48.36	Lm	2,440.19	100mm ht x 20mm thick fair face concrete skirting to match floor	9.4.2
12.0 — التاثيث / القسم 12 - LED / DIVISION 12 - FURNISHING (SIGNAGE, FITTINGS, LED DISPLAY)					
15,500.00	1,550.00	No	10.00	Basement directory signage 500x1000mm; SG01	12.2.1
1,550.00	1,550.00	No	1.00	GF lobby directory 500x1000mm; SG02	12.2.2
6,045.00	604.50	No	10.00	Parking signage; SG06	12.2.3
2,000.00	1,000.00	No	2.00	Information signage; SG07	12.2.4
2,000.00	1,000.00	No	2.00	Lounge signage; SG08	12.2.5
1,000.00	1,000.00	No	1.00	Hotel signage; SG09	12.2.6



8,649.00	576.60	No	15.00	Lift signage; SG10	12.2.7
39,208.80	576.60	No	68.00	Lift cars signage; SG11	12.2.8
4,036.20	576.60	No	7.00	VIP lifts signage; SG12	12.2.9
576.60	576.60	No	1.00	Male prayer room signage; SG18	12.2.10
576.60	576.60	No	1.00	Female prayer room signage; SG19	12.2.11
1,153.20	576.60	No	2.00	Male toilet signage; SG20	12.2.12
1,153.20	576.60	No	2.00	Female toilet signage; SG21	12.2.13
1,153.20	576.60	No	2.00	Accessible toilet signage; SG22	12.2.14
7,905.00	7,905.00	No	1.00	Arabic calligraphy engraving on sandstone panels (ID6-011)	12.2.15
10,044.00	1,674.00	No	6.00	Undercounter washbasin; SW-01	12.3.1
2,511.00	418.50	No	6.00	Soap/air/paper module; SW-02	12.3.2
4,743.00	790.50	No	6.00	Faucet; SW-03	12.3.3
21,762.00	2,418.00	No	9.00	Wall hung water closet w/ cover & concealed flush tank; SW-04	12.3.4
1,339.20	167.40	No	8.00	Toilet roll holder; SW-07	12.3.5
892.80	111.60	No	8.00	Towel hook; SW-08	12.3.6
892.80	148.80	No	6.00	Floor drain; SW-09	12.3.7
10,741.50	976.50	No	11.00	Accessible basin; SW-10	12.3.8
530.10	176.70	No	3.00	Horizontal grab bar; SW-11	12.3.9
706.80	353.40	No	2.00	Vertical grab bar; SW-11	12.3.10
762.60	762.60	No	1.00	Folding grab bar	12.3.11
1,488.00	1,488.00	No	1.00	Closed coupled toilet; SW-12	12.3.12
3,310.80	413.85	No	8.00	Bidette; SW-13	12.3.13
976.50	195.30	No	5.00	Ablution seats	12.3.14
2,901.60	483.60	No	6.00	520x900mm vanity mirror	12.3.15
1,209.00	604.50	No	2.00	850x2000mm safety glass mirror	12.3.16
1,790.25	358.05	No	5.00	Concealed wall mounted garbage bin	12.3.17
300,000.00	300,000.00	No	1.00	Large-format LED display 4K, P1.8, 5780H x 10750W mm, controller Vx16s+i7, media player	12.4.1
13.0 — الأثاث الثابت / FIXED FURNITURE					
23,000.00	23,000.00	No	1.00	Lounge counter F-01	13.01
23,000.00	23,000.00	No	1.00	Serving/cashier desk + kitchenette F-03	13.02
84,000.00	42,000.00	No	2.00	Reception counter F-04	13.03
32,000.00	16,000.00	No	2.00	Vanity counter F-05	13.04
14.0 — أعمال الهدم / DEMOLITIONS					
58,270.50	30.00	lm	1,942.35	Demolition existing walls - Basement 3/2/1 (incl protection, disposal off-site)	14.01
63,870.00	30.00	lm	2,129.00	Demolition existing walls - GF / GF Mezz / First Floor	14.02
188,868.30	30.00	lm	6,295.61	Demolition existing walls - 4th to 20th floor (17 hotel floors)	14.03
385,236.90	30.00	lm	12,841.23	Demolition existing walls - 21st to 56th office floor	14.04
15.0 — أعمال البناء / MASONRY					
364,000.00	70.00	m²	5,200.00	Hollow concrete blockwork 200mm	15.03
612,950.00	115.00	m²	5,330.00	Hollow concrete blockwork 200mm - Elevator walls	15.04
720,844.68	137.00	m²	5,261.64	Hollow concrete blockwork 200mm - 21st to 56th office floor	15.05



10,393,288.65

إجمالي التشطيبات الداخلية (SAR)



عزوم المتحدة | قلب نجد — أعمال اللاندسكيب

الإجمالي Amount	السعر Rate	الوحدة Unit	الكمية Qty	Description (EN)	البند Code
L-A — أعمال اللاندسكيب الصلب / LANDSCAPE - A. HARD LANDSCAPE WORKS					
206,152.82	195.30	m²	1,055.57	200x600x40mm yellow rustic granite, bush hammered, on RC slab - Parking pavement TL9	A.1.1
570,000.00	200.00	m²	2,850.00	600x600x40mm yellow rustic granite, bush hammered, on RC slab - Driveway pavement TL6	A.2.1
245,055.00	79.05	mrn	3,100.00	40x6mm stainless steel edging - Triangular pavement MT1	A.3.1
86,629.50	251.10	m²	345.00	225x600x40mm yellow rustic granite, polished - Triangular pattern TL8	A.4.1
181,815.00	213.90	m²	850.00	20mm Riyadh limestone cladding to perimeter wall, dry fixed SS system - TL13	A.5.1
209,361.60	195.30	m²	1,072.00	600x600x20mm Riyadh limestone antique finish - Building apron TL1	A.6.1
115,000.00	115,000.00	LS	1.00	Grand water cascade RC base/walls 35200x5500x450mm incl waterproofing	A.7.1
88,500.00	300.00	m²	295.00	600x600x20mm black granite polished - Cascade floor/internal wall TL5	A.7.2
30,690.00	279.00	m²	110.00	33x80mm black scale light mosaic matte - Cascade external wall TL14	A.7.3
40,000.00	40,000.00	LS	1.00	Light box lettering '6925' 800x100mm, 29LT Azer Medium, SS frame + acrylic	A.8.1
45,000.00	45,000.00	LS	1.00	Light box lettering 'NJD'S HEART' 6955x825x100mm, Fedra Sans Pro Book, SS frame + acrylic	A.8.2
32,000.00	32,000.00	LS	1.00	Backdrop panel 7800x3700x200mm, welded 50x50x3mm galvanized MS hollow section, epoxy	A.8.3
39,060.00	39,060.00	LS	1.00	20mm granite cladding to backdrop, dry-fix system, concealed SS clips triangular pattern	A.8.4
167,400.00	27,900.00	LS	6.00	Sculpture supply & installation per RFP project identity (internal & external)	A.8.5
139,500.00	139,500.00	LS	1.00	Central water feature RC base/walls 58047x1410x710mm incl waterproofing	A.9.1



32,000.00	320.00	m²	100.00	600x600x20mm black granite polished - Central feature internal wall TL5	A.9.2
20,800.00	320.00	m²	65.00	600x600x20mm black granite polished - Central feature external wall type 1 TL5	A.9.3
17,721.60	320.00	m²	55.38	33x80mm gold scale light mosaic matte - Central feature external wall type 2 TL7	A.9.4
11,250.00	250.00	m²	45.00	Scupper drain 3-5mm SS grating brushed + 15-20mm white gravel - ST1	A.10.1
1,822.80	91.14	mrn	20.00	40mm H, 6mm SS edging on RC planter - MT3	A.11.1
31,900.00	220.00	mrn	145.00	300mm H x 75mm dia car stopper GI powder coated black matte - Safety railing MT2	A.12.1
11,160.00	446.40	m²	25.00	Floating steps tread/riser - 8 pcs 3500x650mm, 170mm riser, RC + 40mm granite TL10	A.13.1
6,640.20	79.05	mrn	84.00	Steps nosing 3mm SS strip inlay - MT1	A.13.2
4,687.20	390.60	mrn	12.00	900mm H x 10mm GI steel rod railing black powder coated - MT4	A.13.3
7,000.00	280.00	m²	25.00	Staircase tread/riser 300x600x20mm yellow rustic granite bush hammered - TL11	A.14.1
17,577.00	83.70	mrn	210.00	Steps nosing 3mm SS strip inlay - MT1	A.14.2
4,185.00	348.75	mrn	12.00	900mm H x 40mm dia GI steel railing black powder coated - MT4	A.14.3
30,829.50	181.35	mrn	170.00	Granite driveway kerb 300x600x150mm chamfered, on concrete bedding - TL12	A.15.1
8,928.00	446.40	m²	20.00	450mm H galvanized steel planter, bronze powder coated - Tiered MT3	A.16.1
8,928.00	446.40	m²	20.00	600mm H galvanized steel planter, bronze powder coated - Tiered MT3	A.16.2
11,160.00	446.40	m²	25.00	900mm H galvanized steel planter, bronze powder coated - Tiered MT3	A.16.3
8,928.00	446.40	m²	20.00	450mm H galvanized steel planter bronze - Gallery dropoff MT3	A.17.1
20,000.00	20,000.00	LS	1.00	Light box lettering '4410' قلب نجد 520x50mm SS frame + acrylic	A.18.1
20,000.00	20,000.00	LS	1.00	Light box lettering 'NJD'S HEART' 4410x530x50mm SS frame + acrylic	A.18.2
59,241.00	2,278.50	nos	26.00	Wayfinding directional signage 270x750x100mm galvanized steel bronze, LED illuminated	A.19.1
11,680.80	730.05	nos	16.00	Circular bollard 100mm dia x 900mm H x 3mm SS	A.20.1
6,696.00	446.40	m²	15.00	450mm H galvanized steel planter bronze - SW corner MT3	A.21.1
6,696.00	446.40	m²	15.00	600mm H galvanized steel planter bronze - SW corner MT3	A.21.2
8,928.00	446.40	m²	20.00	900mm H galvanized steel planter bronze - SW corner MT3	A.21.3
20,769.03	20,769.03	LS	1.00	Light box lettering '4410' قلب نجد 520x50mm SS frame + acrylic - SW corner	A.22.1
22,000.00	22,000.00	LS	1.00	Light box lettering 'NJD'S HEART' 4410x530x50mm SS frame + acrylic - SW corner	A.22.2
L-B — أعمال اللاندسكيب الناعم / LANDSCAPE - B. SOFT LANDSCAPE WORKS					
75,097.50	158.10	m³	475.00	Soil mix for planter (Perlite/Pumice 30%, Cocopeat 30%, Compost 20%, Conditioner 15%, Sand 5%)	B.1.1
10,350.90	195.30	nos	53.00	Quad staking for trees >300mm dia, 4 MS steel 75x75x2400mm powder coated	B.1.2
26,040.00	37.20	m²	700.00	25mm draincell to floor/wall of planter box + geotextile	B.1.3
10,843.80	204.60	nos	53.00	Underground tree anchoring D-MAN modules (Elmich or equal)	B.1.4
9,300.00	2,325.00	nos	4.00	Olea europea (Olive Tree) TD1200mm OH3m	B.2.1



18,739.50	1,441.50	nos	13.00	Chamaerops humilis (European fan palm) TD200mm OH3.5m multitrunk	B.2.2
35,154.00	1,674.00	nos	21.00	Terminalia arjuna (Arjun tree) TD200mm OH5m	B.2.3
45,000.00	3,000.00	nos	15.00	Phoenix dactylifera (Date palm) TD600mm OH10m	B.2.4
24,045.00	21.00	nos	1,145.00	Leucophyllum frutescens (Barometer bush) OH450mm	B.2.5
15,435.00	21.00	nos	735.00	Atriplex halimus (Mediterranean saltbush) OH450mm	B.2.6
42,840.00	21.00	nos	2,040.00	Clerodendrum inerme (Wild Jasmine) OH450mm	B.2.7
45,045.00	21.00	nos	2,145.00	Lawsonia inermis (Henna) OH450mm	B.2.8
94,860.00	94,860.00	LS	1.00	Auto-irrigation system complete (equivalent to Urban Hydro spec)	B.3.1
7,161.00	1,023.00	nos	7.00	Rain Bird ESP-RZXE irrigation control box timer	B.3.2
3,580.50	511.50	nos	7.00	Rain Bird 100 DV 1" control valve in valve box	B.3.3
8,549.30	18.60	mrn	459.64	16-18mm OD subsurface drip tubing	B.3.4
2,278.50	325.50	nos	7.00	1" water inlet/tap point	B.3.5
737,583.00	102.30	m²	7,210.00	Leveling RC slab 10cm (300 kg/cm²) + lightweight concrete ribs, voids w/ foam, waterproofing	B.4.1

3,819,595.06

إجمالي أعمال اللاندسكيب (SAR)



عزوم المتحدة | قلب نجد — أعمال الإنارة

الإجمالي Amount	السعر Rate	الوحدة Unit	الكمية Qty	Description (EN)	البند Code
LT-A — أ. توريد الوحدات / الإنارة - A. SUPPLY OF FIXTURES					
17,153.85	490.11	nos	35.00	Underground Light UP1 - SIMES S.5681W.14, LED 2W 330lm 3000K, IP67	LT.1
6,877.35	458.49	nos	15.00	Underground Light UP2 - SIMES S.5683W.14, LED 2W 330lm 3000K, IP67	LT.2
30,623.04	624.96	nos	49.00	Spot Light SP1 - UL-5933, AC LED 20W 1160lm 38° 3000K, IP65	LT.3
17,668.14	384.09	nos	46.00	Wall Light WL1 - UL-6071 Luna ramp recessed, LED 7.2W 180lm 3000K, IP65	LT.4
8,632.26	411.06	nos	21.00	Wall Light WL2 - UL-5061 Mini Mira up/down, LED 14W 960lm 18° 3000K, IP66	LT.5
10,685.70	356.19	nos	30.00	Wall Light WL3 - UL-5060 Mini Mira down, LED 8W 810lm 104° 3000K, IP66	LT.6
63,218.61	1,620.99	nos	39.00	Pole Light PL1 - UL-7780 Korner1, LED 38W 4210lm T3 3000K, IP66, alu pole 4500mm	LT.7
3,359.65	671.93	nos	5.00	Radius Linear Light RL1 - SIMES S.5402W, LED 8.1W 1260lm 3000K, IP67	LT.8
12,608.62	434.78	nos	29.00	Linear Light LL2 - LS-MST-XY6025, LED 18W 1620lm 25° 24VDC 3000K, IP66	LT.9
27,683.31	268.77	nos	103.00	LED Strip Light LED1 - LS-MAWLM-3528, 4W/m 3000K 24V, IP67 + Meanwell drivers	LT.10



17,643.96	284.58	nos	62.00	LED Strip Light LED2 - LS-MPLW-T120, 9W/m 3000K 24VDC, IP65 + Meanwell drivers	LT.11
9,296.28	332.01	nos	28.00	LED Strip Light LED3 - LS-LLS14, 9W/m 3000K 24VDC, IP68 + SS housing	LT.12
13,280.40	1,106.70	nos	12.00	Bollard Light BL4 - LEDS-55-E088, LED 16.3W 729lm 105° 3000K CRI90, IP66	LT.13
LT-B — (الداخلي) الإنارة - ب. التركيب (الداخلي) / LIGHTING - B. INSTALLATION (INTERIOR)					
92,881.40	197.62	No	470.00	LED down light single height areas - Luxo 3 Basic CoB black 10W 600lm 3000K (7702 4.7)	LB.1
17,074.80	94.86	Lm	180.00	Surface mounted LED strip light (7705 4.15-4.14)	LB.2
65,100.00	32,550.00	Item	2.00	Custom Chandelier type 1 incl downlights - GF Lobby South (7702 4.9)	LB.3
65,100.00	32,550.00	Item	2.00	Custom Chandelier type 2 incl downlights - GF Mezzanine (7702 4.10)	LB.4
32,550.00	32,550.00	Item	1.00	Custom Chandelier type 3 incl downlights - GF VIP lift Lobby (7702 4.11)	LB.5
671.93	671.93	No	1.00	Touch pad (Ground floor)	LB.6
24,743.58	233.43	No	106.00	Motion sensor point	LB.7
11,383.20	1,422.90	No	8.00	LCP (Lighting control panel)	LB.8
9,090.75	9,090.75	LS	1.00	Circular Panel Lighting	LB.9
101,184.00	252.96	m²	400.00	Back lighting to stretch membrane ceilings (7702 4.6)	LB.10
658,510.83 (إجمالي أعمال الإنارة (SAR))					





التنفيذ والتسليم وحدود المسؤولية

EXECUTION, DELIVERY & RESPONSIBILITIES

التنفيذ والتسليم

- مدة تنفيذ الأعمال حسب ما يتم الاتفاق عليها عند توقيع العقود.

حدود مسؤولياتنا

تلتزم شركة عزوم المتحدة للمقاولات بتوفير العمالة الماهرة والمؤهلة مع توفير المواد اللازمة لتنفيذ البنود وفقاً لما ذكر في جداول الكميات ضمن نطاق المشروع، وذلك وفق أعلى معايير الجودة والسلامة المعتمدة. وتشمل مسؤوليات شركتنا:

- توفير العمالة الفنية المتخصصة.
- توفير المواد.
- توفير المعدات والأدوات اللازمة للتنفيذ.
- الإشراف الفني على العمالة.
- تنفيذ الأعمال حسب المخططات والمواصفات.
- الالتزام بإجراءات السلامة داخل الموقع.





شروط الدفع وجدول الدفعات

PAYMENT TERMS

شروط الدفع

- الالتزام بسداد الفواتير خلال مدة أقصاها 15 يوماً من تاريخ استلام الفاتورة.
- أي تأخير في الدفع يؤثر على سير العمل بالمشروع.

جدول الدفعات

- 20% دفعة مقدمة من قيمة العرض عند توقيع العقد.
- يُقسَّم باقي المبلغ على دفعات (مستخلصات) حسب نسبة الإنجاز أو حسب ما يتم الاتفاق عليه.
- في حالة الدفعة المقدمة يتم اصدار ضمان بنكي غير مشروط من قبل المقاول يساوي قيمة الدفعة المقدمة.





نقاط التواصل والاستفسارات

POINTS OF CONTACT

المستوى	الاسم	المنصب	التواصل
المستوى الأول	م. يحيى آل سلامة	الرئيس التنفيذي	0500077006 yahya@Azoomunited.com
المستوى الثاني	م. وليد مرجونه	مدير المشاريع	0507341903 waleed.m@azoomunited.com



شركة عزوم المتحدة للمقاولات · AZOOM United Co